BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

BBMP/2024-25/OW/WORK_INDENT6873

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No:EE/YNK-D/KPPP/16/2024-25 Dated: 10/03/2025

APPROVED TENDER SCHEDULE - B

Name of Work:- Resurfacing of roads at Manavarthi thota main and cross roads in chowdeshwari ward no -02

Item-06

Sl	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri.VEERESH K P(SRI VEERABHADRESHWARA CONSTRUCTIONS)	
				Rate	Rate in Words
1	Removing And Resetting Of Footpath Slab [Approved Rate]	Sqm	324.90	242.00	Two Hundred FourtyTwo Only
2	Earth work excavation by manual means for drains,canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such simillar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work . Loading and Unloading of Stone Boulder/Stone aggregates/Sand/Kankar/Moorum.(Tipper 14 m3) complete as per the direction of Engineer In charge of the work	Cum	376.39	371.50	Three Hundred SeventyOne Paise Fifty Only
3	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately) Mix 1:3:6 (M10) Using 40 mm nominal size graded crushed coarse aggregates complete as per the direction of Engineer In charge of the work	Cum	37.50	6784.00	Six Thousand Seven Hundred EightyFour Only
4	Supplying, Fitting and Placing un-coated TMT bar Reinforcement in sub-structure complete as per Drawing and Technical Specifications.complete as per the direction of Engineer In charge of the work	Tonne	4.39	89502.00	EightyNine Thousand Five Hundred Two Only

Sl	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri.VEERESH K P(SRI VEERABHADRESHWARA CONSTRUCTIONS)	
				Rate	Rate in Words
5	Providing and laying in position Reinforced cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necesary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork to be paid separately) M20 Design Mix Using 20 mm nominal size graded crushed coarse aggregates complete as per the direction of Engineer In charge of the work	Cum	87.87	7520.50	Seven Thousand Five Hundred Twenty Paise Fifty Only
6	Providing and fixing precast reinforced cement concrete covering slabs of 10Cm thick made of M20 with OPC cement, with 20mm and down size graded granite metal coarse aggregate @0.70cum and fine aggregate & 0.74 cum with superplasticizer machine,mixed, Inculding providing and removing centering, shuttering, strutting propping etc., for edges of slabs with TMT steel (Fe500) cost of all materials, labour, all lead and lift, HOM of machinery, curing, including cost of reinforcement etc., complete as directed by the Engineer in charge of the work	Sqm	268.73	2134.00	Two Thousand One Hundred ThirtyFour Only
7	Dismantling of cement concrete pavement by mechanical means using pneumatic tools, breaking to pieces not exceeding 0.02 m3 in volume and stock piling at designated locations and disposal of dismantled materials and stacking serviceable and unserviceable materials separatelcomplete as per the direction of Engineer In charge of the work	Cum	168.31	638.00	Six Hundred ThirtyEight Only
8	Earth work in surface excavation by mechanical means for lowering & leveling the ground for all works other than foundation in all kinds of soils & upto depth not exceeding 300mm as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter including dressing of excavated surfaces, disposing off or levelling the excavated earth or sorting & stacking the selected earth for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools, usage of machinery & other appurtenances required to complete the workcomplete as per the direction of Engineer In charge of the work	Cum	99.45	107.00	One Hundred Seven Only

from the Competent Authority.

Division

	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri.VEERESH K P(SRI VEERABHADRESHWARA CONSTRUCTIONS)	
				Rate	Rate in Words
9	Construction of dry lean cement concrete Sub- base over a prepared sub-grade with coarse and fine aggregate conforming to IS: 383, the size of coarse aggregate not exceeding 25 mm, aggregate cement ratio not to exceed 15:1, aggregate gradation after blending to be as per table 600-1, cement content not to be less than 150 kg/ m3, optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in a batching plant, transported to site, laid with a paver with electronic sensor, compacting with 8-10 t vibratory roller, finishing and curing. complete as per the direction of Engineer In charge of the work	Cum	193.55	5573.00	Five Thousand Five Hundred SeventyThree Only
10	Providing and constructing un-reinforced plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement or any other type as per Clause 1501.2.2 M30 (Grade), coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a concrete mixer of not less than 0.2 cum capacity andappropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including construction joints, , primer, sealant , curing of concrete slabs for 14- days, and water finishing to lines and grade as per drawing and technical specification clause 1501 with all lead, lifts, loading & unloading charges, cost and conveyance of all materials, labour, equipments etc., complete. as per the directions of the Engineer-in-charge of the work.complete as per the direction of Engineer In charge of the work	Cum	241.94	7650.00	Seven Thousand Six Hundred Fifty Only
11	Cost of Haulage Excluding Loading and Unloading Taking output 25 t load and lead 10 km = 100 t.km complete as per the direction of Engineer In charge of the work	T.Km	962.53	91.00	NinetyOne Only

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.

Executive Engineer
Bruhat Bengaluru Mahanagara Palike
Yelahanka, Division

Veeresh K.P
[SRI VEERABHADRESHWARA CONSTRUCTIONS]

...the Competent Authority.

...elahanka, Division